



CALAMBA WATER DISTRICT

Lakeview Subdivision, Halang, Calamba City
Tel. Nos.: (049) 545-2863; 545-1614; 545-7895; 545-7981; 545-1389; 545-2728
Fax: (049) 545-9752

PROJECT :PROPOSED BUILT IN CABINET
LOCATION :Ground Floor, CWD Main Building, Lakeview Subd., Brgy. Halang, Calamba City
DATE :April 5, 2021

SCOPE OF WORKS AND SPECIFICATIONS

I. SCOPE OF WORKS

The work calls for the performance to supply of labor, materials, tools and other appurtenances necessary to complete the above project as shown on the drawings and as specified herein.

A. Preliminary

The Contractor shall measure/check the available wall space and verify the dimensions of the cabinet stated in the drawing. Any changes to suit field condition shall be as per approval by the Engineer.

B. Construction of Cabinet

The Contractor shall construct the cabinet according to the approved location and dimensions. Materials to be used shall be according to the standard specifications.

C. Finishing

Interior of the Cabinet - The Contractor shall paint the interior of the cabinet.

Exterior of the Cabinet – The Contractor shall use Formica for the exterior side of the Cabinet. The Contractor shall submit samples of Formica, for approval of the Engineer.

D. Hinges and Cabinet Door Handle

The Contractor shall use Soft-closed Concealed Hinge. The Contractor shall also submit sample of door handle, for approval of the Engineer or End-user.

II. MATERIAL SPECIFICATION

1. Marine Plywood $\frac{3}{4}$ " ordinary
2. Marine Plywood $\frac{1}{2}$ " ordinary
3. Formica
4. Adhesive – Contact Cement
5. Enamel Paint QDE – Offwhite